Birla Industrial & Technological Museum



(National Council of Science Museums, Ministry of Culture, Govt. of India)



19A, Gurusaday Road, Kolkata - 700 019

Sub: Providing and laying of PVC flooring in Transport Gallery at BITM, Kolkata.

Sl. No.	Description of item	Qty.	Unit	Rate	Amount
1.0	Proving and laying of 3 mm thick Luxury High Performance Vinyl				
	Plank PVC Flooring conforming to manufacturers with PUR guard				
	including filling pot holes wherever necessary, installation of accessories such as edge packing PVC/wooden beading, using				
	appropriate bonding agent to adhere with the existing flooring,				
	laying in required pattern including wastage etc. all complete as				
	directed by Engineer-in-charge etc complete. Make: Wonder Floor				
	(Timberland Maestro) (No other make will be considered) after				
	removing existing flooring laid in floor including cutting, folding				
	and stacking in desired location as per the instructions of Engineer-				
	in-charge all complete and also preparation of surface before laying				
	of PVC flooring including vacuum cleaning, rubbing grinding (if				
	necessary) removing of all undulations and filling of pot holes if any				
	with non-shrink cementitious grout final rubbing to make entire floor surface even and ready to lay PVC flooring all complete as per				
	instructions of Engineer-in-charge.				
	Note:				
	1. Providing a physical sample before mobilization of all resources				
	at site is mandatory.				
	2. One plank is required to be pasted and showing it to Engineer In				
	Charge is necessarily required.	425	Sqm.	1,054.59	448200.75
Basic value of the work = Say Rs. Add GST @18% over basic value of work = Cost of work including GST =				4,48,200.75	
				4,48,201.00	
				80,676.00	
				5,28,877.00	
Add Labour welfare cess @1% over cost of work including GST =				5,289.00	
Gross value of work including GST @18% & LWC @1% =					5,34,166.00

NOTE:

- 1 Tenderers should visit the site before quoting the rate to understand the nature of work and condition of the site.
- 2 Rates shall be quoted inclusive of all materials, **wastage**, labour, shifting charges, **taxes & duties** etc. required for this job. No additional payment shall be made by the BITM for this purpose.
- The work shall be required to carry out without obstructing the visitors' movements and may also be required to carry out beyond office hours (if required) for which no additional payment shall be made.
- 4 Regarding the work directives of the Engineer-in-Charge shall be final and binding.
- 5 All materials must be approved by the Engineer-in- Charge before supplying at site. List of Approved materials:
 - i) PVC Flooring: Wonder Floor (Timberland Maestro)